BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No. RRND/EE/Tend/10/2015-16, Date: 19.11.2015

E-procurement No: BBMP/2015-16/BD/WORK_INDENT18226

SCHEDULE -B

Name of Work : Construction of Gym and Yoga building at Sundar nagara and Mineral water Unit in ward no 17

Sl. No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	426.37	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.	cmt	250.00	Rupees Two Hundred Fifty Only
2	37.14	Providing and laying plain cement concrete of mix M7.5 with OPC cement @180kgs with 40mm and down size graded granite metal, coarse aggregates @0.86cum and fine aggregates @0.568cum machine mixed, concrete laid in layers not exceeding 15 crns.. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cmt	4500.00	Rupees Four Thousand Five Hundred Only
3	48.60	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @320 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregtes@ 0.459cum, with superplatisiser @3lts confirming to ISO 103-1999 Reaffirmed -2008,machine mixed, concrete laid in layers not exceeding 15 cms thick vibrated for all works in foundation for footings & pedestals retaining walls, return walls, walls(any thickness including attached plasters, columns, piers, abutments, pillars, pots, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc.., including cost of materials, labour, HOM of machinery, curing, complete as per specification.	cmt	6750.00	Rupees Six Thousand Seven Hundred Fifty Only

Signature of the contratror

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

103	172.00	Providing and laying intergral cement based waterproofing treatement including preparation of surface as required for teatment of roofs balconies,terraces etc., consisting of i) Applying and grouting a slurry coat of neat cement coat using 2.75kg/smt of cement and mixed with proprietary water proofing compound confirming to IS 2645 over the RCC slab including cleaning the surface before treatment. ii) Laying cement concrete using broken well saturated brickbats 25mm to 100mm size with 50% of CM 1:5 cement 43 grade and mixed with proprietary waterproofing compound conforming to IS 2645 to required slope, and treating similarly adjoining walls upto 300mm height including rounding of junctions of walls/Slabs.The brickbats are to be flooded with standing water for two days and the dissolved brick bats are to be replaced with well burnt standard brick bats. iii) After two days of proper curing applying a second coat of cement slurry admixed with proprietry waterproofing compound conforming to IS 2645 iv) Finishing the surface with 20mm thick jointless CM 1:4 admixed with proprietary waterproffing compound conforming to IS 2645 and finally finishing the surface with trowel with neat cement	Smt	1000.00	Rupees One Thousand Only
104	500.00	Providing and laying heavy duty cobble stones 60mm thk interlock pavers using cement and course sand for manufacture of blocksd of approved size shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thk sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints final compaction of pavers surface joints into its final level,including cost of materials, labour, HOM of machineries complete as per specifications.	Smt	1000.00	Rupees One Thousand Only
105	70.00	supplyinhg and installation of glazing for front elevationwith necessary equipments for successful completion of the work and as per direction of the engineer -incharge etc., complete.(MR)	smt	4045.00	Rupees Four Thousand Forty Five Only

nature of the contratror

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner